Whereas Lakkavalli Rajubayi, resident of Sorab, claiming to be the daughter of the said Lakkavalli Venkubayi, deceased, has applied to this Court for a certificate under Act VII of 1901 to collect debts payable in respect of the estate of Lakkavalli Venkubayi, deceased, resident of Shimoga.

Notice is hereby given of the said application; and all claimants in the estate of the said Lakkavalli Venkubayi, deceased, are invited to appear in this Court on Tuesday the 12th day of February 1907, when the petition of the said Lakkavalli Rajubayi, applicant, will be heard and the right to the certificate will be determined.

Given under my hand and the seal of this Court, this the 7th day of January 1907.

B. S. KRISHNASWAMAIENGAR, *Subordinate Judge.*

MYSORE DIVISION.

The 7th January 1907.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 4th February 1907, for restoring the Bukenkere tank Registered No. 152 of Krishnarajpete Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1908.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for restoring the Bukenkere tank, Registered No. 152, Krishnarajpete Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Detailed abstract estimate of restoring the Bukenkere tank, Registered No. 152 of Krishnarajpete Taluk :—

Items of work	Per	Quantity
Bund.		
Earthwork including consolidation	Cyd.	22,481
Turfing	Sqr.	1,311·75
Gravelling over top of bund	Cyd.	400
Grade stone with bed slabs	Each	37
Top width stone	Do	37
Registered No. stone	Do	1
Bench mark stone	Do	2
Gauge No. stone	Do	1
New stone pitching 3 to 1 slope	Cyd.	1,983
Old stone do	Do	1,019
New stone work	Do	729
Clearing jungle and benching	L. S. Rs.	...
Gravel backing to revetment	Cyd.	182
Total	...	...
Sluices.		
Examining the sluice...	L. S. Rs.	..
Right Waste-weir 175 feet long.		
Benching rock (3 inches thick)	Sft.	772
Brick in surki mortar	Cft.	3,465
Burnt stone slabs neatly dressed, closely fitted and pointing with cement	Sft.	497
Plastering with surki mortar	Sqr.	22·97
Clearing site	L. S. Rs.	...
Constructing core wall	Do	...
Total	...	

V. V. KARVE, for *Executive Engineer.*